

Standard Building Specifications Base Model

June 1, 2021

ENERGY EFFICIENCY:

- All homes are EnerGuide rated with air tightness test and Labelled
- ♦ Premium LED lighting package
- Insulation:
 - Batt R20 exterior & frost walls
 - Sealed R20 joist spaces
 - Blown-in R50 attic
 - Batt R28 floor over garage
- ♦ Insulated and sealed attic access
- ♦ Spray-foam sealant at all attic penetrations
- Windows:
 - Triple pain Clear/Clear/LowE
 - Egress compliant in bedrooms and basement

STRUCTURAL:

- ♦ Engineered foundation is 8'-4" tall
- Engineered floor systems
 - Main Floor I-Joists
 - Second Floor OWWJ
- ♦ Engineered roof trusses
- ♦ Engineered tall wall design as required
- Perimeter weeping tile terminated in sump pit with pump
- ♦ Exterior walls 2x6 construction as per plan
- Floating frost walls 2x4 construction as per plan
- ♦ Interior ceiling Height:
 - 9' main floor
 - 8' second floor

EXTERIOR:

- ♦ Sealed exterior concrete
- Broom finish on garage floors, sidewalks and driveways
- ♦ Driveway width matches garage width
- ♦ Builder's Standard Architectural Shingles
- Back deck ledger provided for future deck as per plan
- Rough grading provided to property. Topsoil NOT included.
- Builder's standard insulated steel overhead garage door
- Builder's standard vinyl: siding, shakes and board & batten
- Builder's standard manufactured stacked stone
- ♦ Builder's standard low maintenance trim

ELECTRICAL:

- ♦ Electrical panel installed at point of entry
 - 100 amp service
 - 64 circuit breakers
- Cat5 & Coax outlets in Great Room, all Bedrooms and Bonus Room
- Dual USB outlet in Kitchen & Master Bedroom (2)
- ♦ White Decora plugs and switches
- Hard wired smoke and carbon monoxide detectors as required
- Basement outlets for mechanical equipment only

June 4, 2021 Page 1 of 2

PLUMBING/MECHANICAL:

- ♦ Engineered mechanical design
- Builder's standard high efficiency furnace
- ♦ Honeywell Wi-Fi programmable thermostat
- Builder's standard natural gas 50 US gallon hot water tank
- Builder's standard HRV with low voltage timer controls
- ♦ Exterior hose bib front & rear
- ♦ Basement bathroom rough-ins
- In line sewer back-check water valve
- Builder's standard plumbing fixtures
 - Comfort height dual flush toilet
- ♦ Builder's standard faucets
 - Pressure balanced faucets at tubs and showers
- Towel bars & paper holders to match faucets
- ♦ Builder's standard sliding shower doors
- Central vacuum rough-ins on main & second floor

CABINETRY:

- ♦ Professionally designed cabinet layout
- ♦ Quartz countertop on all cabinets
- ♦ Kitchen upper cabinets 36" tall
- ♦ Enlarged OTR cabinet
- ♦ Fridge cabinet 24" deep with gable
- Fridge opening to accommodate 36" wide fridge
- ◆ OTR & range opening to accommodate standard 30" range/OTR
- Soft close door and drawer hardware throughout

INTERIOR FINISHINGS:

- Builder's standard tile trim around tubs/showers
- Smooth finish painted hollow core interior doors with 3 hinges as per plan
- ♦ Door hardware
 - Satin nickel
 - Halifax lever exterior
 - Troy knob interior
 - Privacy locks on all bathrooms and master bedroom
 - Deadbolt lock with passage lever on all exterior and garage doors
- ◆ Paint
 - Walls 1 coat primer & 2 coats finish
 - Walls Dulux eggshell finish
 - Trim Dulux pearl finish
 - Interior doors Dulux pearl finish
- ♦ MDF baseboards and casing
- ♦ MDF capped stubwalls (42" high)
- Mirrors installed to meet countertop
- Wire shelving in pantry and closets
- ♦ Luxury vinyl flooring
 - Planks entire main floor
 - Tiles second floor laundry and baths
- Carpet on stairs and second floor with 8lb underlay
- ♦ Square corner drywall bead

GENERAL INFORMATION:

- ◆ All homes are built in accordance with the National Building Code of Canada and all local requirements & standards
- ♦ All homes are covered by Pacesetter Homes one year "Builder Warranty" and enrolled with a certified Warranty Program providing a ten-year structural warranty upon date of possession
- Concrete floors, driveways/sidewalks, parking pads and general grading are affected from: soil conditions, salt and/or frost heaving; therefore, no guarantee, related to these causes, can be given by Pacesetter Homes

June 4, 2021 Page 2 of 2